

ANAND AGRICULTURAL UNIVERSITY
ANAND

Name of work :- Construction of protection wall to Girls hostel at AAU, Jabugam.

REFERENCE SHEET

Sr No	Tender It. No	Description of item	Vol	Page No	Item No	Para No	Remarks
1	1	Boring holes 2.5 mt. depth in ordinary soil (for cast in situ piles) for 250mm dia piles etc complete	1	36	4.27(ii)	1.0 to 2.2	-
2	2	Under Reaming inside the bore holes for under reamed piles of 250 mm dia	1	36	4.28(ii)	1.0 to 2.3	-
3	3	cement concrete 1:2:4 (1cement : 2 coarse sand : 4 graded stone 20 mm nominal size) for CC work for piles	1	40,41, 42,43	5.3.13	1.0 to 4.3	-
4	4	Excavation for foundation in loose of soft soil 1.50 mt. depth	1	29	4.0.0(A)	1.0 to 6.2	Read all lead & lift instead of 50m lead
5	5	Providing and laying cement concrete 1:4:8	1	38	5.3.3. (A)	1.0 to 3.2	-
6	6	cement concrete 1:2:4 mix (1 cement : 2 coarse sand: 4 graded stone aggregate 20mm nominal size of B.T. Kapchi) for R.C.C Ground Beam	1	40,41, 42,43 65	5.3.13 9.1(H)(1)	1.0 to 4.3 1.0 to 2.2	-
7	7	Fe-500 T.M.T. bar steel	1	45	5.4.11	1.0 to 3.2	Read T.M.T bar instead of HYSD bars
8	8	cement concrete 1:2:4 mix (1 cement : 2 coarse sand: 4 graded stone aggregate 20mm nominal size of B.T. Kapchi) for R.C.C Column	1	49	5.006(B)(I)	1.0 to 2.2	-
9	9	Cement Concrete 1 : 1½ : 3 for Coping	1	43,44 65,66	5.4.1 (C) 9.1 (I)(i)	1.0 to 2.3 1.0 to 2.2	Read RCC 1:1.5:3 instead of 1:2:4
10	10	brick work in Super structure in cement mortar 1:6	1	51 53,54	6.13 (B) 6.20	1.0 to 3.2 1.0 to 2.3	Including curing,racking out jts in true line lvl
11	11	15mm thick smooth cement plaster on Wall	1	120 121	17.58 (ii) 17.69	1.0 to 2.2 1.0 to 2.3	Read 15mm th. Instead of 10mm th. Item shall be carried out by fixing chicken net jali of 100mm to 150mm strip at joint of masonry & RCC
12	12	Providing and applying three coats of white washing with lime on wall surface	1	125,126 126,127	18.11 18013	1.0 to 3.9 1.0 to 2.2	-
13	13	0.95m high SS razor wire fencing using 1.70 mt long MS angle 40 x 40 x 6mm size as a pole	II	-	-	-	-
14	14	M.S iron compound gate using the frames of Pipes, channels, angles and flat ,oil paint raw silk shed of asian/berger	1	76 140	10.100(A) 19.19	1.0 to 3.2 1.0 to 3.2	-

Contractor

Executive Engineer